

Final Red Bridge Raise Scheduled for Friday, January 27th (Weather Permitting)

As of January 25th, the Red Bridge has been raised about 4 feet. The remaining and final 6 inches of raising is scheduled for this Friday, January 27th (weather permitting). Approximately 30 hydraulic jacks in total, each with the lifting capacity of approximately 55 tons (note: a typical car jack has a lifting capacity of 1.5 to 3 tons), are used to raise the bridge along with the use of cranes.

